

William R. Bennett Bridge

Intelligent Transportation Systems



Existing Kelowna Bridge

- Existing 3 lane bridge now 50 years old
- Traffic volumes now exceed bridge capacity
- Repairs are no longer on option
- Province of BC determines new bridge required (2003)




New Bridge Proposed

- Province of BC issues Request for Expressions of Interest in October 2003 to initiate selection process for public/private partnership.
- Contractor to design, build, finance and operate new 5 lane bridge



William R. Bennett Bridge

New Bridge - Project Time Line



William R. Bennett Bridge



DMD & Associates



DMD & Associates

Bridge Construction - Pictorial Time Line



August 2006 August 2006



February 2007



August 2007



February 2008

William R. Bennett Bridge

DMD & Associates

DMD & Associates

Electrical / ITS

Design Requirements Overview

- Power Distribution
- Emergency Power
 - UPS for key components
 - Provision for connection of generator
- Lighting
 - Roadway lighting
 - Navigation, Pontoon and Pier Lighting
- Communications
- Closed Circuit Television (CCTV)
- Traffic Detection & Monitoring
- Instrumentation

Bridge Photos – Electrical & Utilities




William R. Bennett Bridge

DMD & Associates

DMD & Associates

Bridge ITS Components Overview

- Closed Circuit Television (CCTV)
 - 10 Fixed Cameras
 - 4 Pan, Tilt, Zoom (PTZ) Cameras
 - Digital Video Recorder
- Vehicle Detection Traffic Counter/Classifier
- Instrumentation
 - Anemometer and Data Logger
 - Road Weather Information System (RWIS)
 - Seismograph recorder and sensors
- Intelligent Roadway Lighting
- Communications System



ITS Components – Cabinet 1



William R. Bennett Bridge

DMD & Associates



Optelecom Ethernet Switches & Encoders



Video & Data Surge Protection
Fibre Patch Panel

DMD & Associates

ITS Components – Cabinet 1




Campbell Scientific Data Logger



Thermostat & Surge Protection

ITS Components – Cabinet 2

Transformer – 347/600 to 120/240 →



PTZ Data Surge Protection

Video Surge Protection

Fibre Patch Panel

ITS Components – ITS Cabinet

Video images on monitor



Digital
Video
Recorder




Router & Video Distribution Amplifiers



Optelecom Decoders – Rear View


ITS Components – Cabinet 3



Multi-Mode
Fibre Cable

Coax Cables

Ethernet Cable




RS422 Cable
For PTZ

ITS Components – Traffic Count Cabinet



Traffic Counter Classifier



Inductive Loop Connections

ITS Components – Fixed Cameras



ites



Testing Fixed Cameras at DMD

ITS Components – Pan, Tilt, Zoom Cameras

- Pelco Esprit PTZ cameras used
- 3 PTZ cameras dispersed across bridge
- 1 PTZ camera under bridge
- Cameras controlled by Vicon Digital Video Recorder software

DMD & Associates




PTZ Camera Testing at DMD

ITS Components

Anemometer & Data Logger



William R. Bennett Bridge



Anemometer & Data Logger being Tested at DMD

ITS Components

Seismic Monitoring System

- GeoSig model CR5 data recorder used
- Sensors
 - 2 Tri-axial force balance accelerometer
 - 1 Tri-axial force balance down hole accelerometer
 - 3 Horizontal Uniaxial force balance accelerometer



DMD & Associates


ITS Components

Road Weather Information System (RWIS)

- RWIS system cabinet will be mounted on the Kelowna side of the bridge
- RWIS system includes the following components
 - 2 pavement sensors
 - Subsurface temperature probe
 - Independent anemometer
 - Temperature / humidity sensor

DMD & Associates

Adaptive Street Lighting System



ITS Components

System Integration Testing

■ Equipment Tested

- Setup Camera and ITS cabinets, fixed and PTZ cameras, data logger etc. at DMD
- Configured all ITS equipment as required
- Debug system
- Performed System Integration Test

■ Tests Performed

- Communications
- Video
- Equipment Functionality
- Environmental Testing



DMD & Associates



ITS Components

System Configuration, Operation and Testing

- Digital Video Recorder (DVR)
 - On site functionality
 - Viewing video
 - Recording Video
 - Remote workstation functionality
 - Viewing Video
 - Recording Video
- Testing of Pan, Tilt, Zoom cameras
- Data Logger and Anemometer
 - Set up sample program and tested wind speed

ITS Components- System Integration Test

 DMD & Associates Ltd.		 WILLIAM BENNETT BRIDGE SYSTEM INTEGRATION TEST	
<h2>Table of Contents</h2>			
1	Introduction.....	1	
2	Scope.....	1	
3	Equipment Tested.....	1	
4	System Integration Test Overview.....	2	
5	System Integration Test.....	2	
5.1	Testing Equipment Used.....	2	
6	Cabinet 1 Equipment.....	2	
6.1	Communications Connectivity Test Results.....	3	
6.2	Data Logger / Anemometer - Wind Speed / Wind Direction Logging Test.....	3	
6.3	Anemometer Test Results.....	3	
6.4	Environmental Testing Procedure.....	4	
6.5	Environmental Test Results - Cabinet 1.....	4	
7	Cabinet 2 Equipment.....	4	
7.1	Communications Connectivity Test Results.....	4	
7.2	Equipment Environmental Testing Procedure.....	5	
7.3	Environmental Testing Results - Cabinet 2.....	5	
8	Cabinet 3 Equipment.....	5	
8.1	Communications Connectivity Test Results.....	5	
8.2	Equipment Environmental Testing Procedure.....	6	
8.3	Environmental Testing Results - Cabinet 3.....	6	
9	ITS Kiosk Equipment.....	6	
9.1	Communications Connectivity Test Results.....	6	
9.2	Pelco Fixed Day/Night Camera Tests.....	7	
9.3	Pelco Fixed Day/Night Camera Test Configuration Results.....	8	
9.4	Pelco Camera Enclosure Environmental Testing Procedure.....	8	
9.5	PTZ Camera Tests.....	12	
9.6	PTZ Camera Test Procedure - PTZ Position.....	12	
9.7	PTZ Camera Test Results - PTZ Pan, Tilt and Zoom Control.....	13	
9.8	PTZ Camera Preset Test Procedure.....	14	
9.9	PTZ Camera Preset Test Results.....	14	
9.10	PTZ Camera Focus Test Procedure.....	14	
9.11	PTZ Camera Environmental Testing.....	15	
9.12	Axis Video Server.....	15	
9.13	Video Transmission Test Procedure.....	15	
9.14	Video Transmission Test Results.....	15	

 DMD & Associates Ltd.		 WILLIAM BENNETT BRIDGE SYSTEM INTEGRATION TEST	
9.15	Koltec Video Data Recording and Playback Test Procedure.....	16	
9.16	Koltec Video Data Recording Playback Results.....	16	
10	Traffic Counting/Classifier Cabinet Tests.....	16	
10.1	Markem 660 Calculation of File Capacity.....	18	
11	IP Device Address Table.....	19	

Conclusion

- When ever possible, equipment set up, configuration, troubleshooting and testing should be performed in a controlled environment
- Why?
 - Verifies integrity of system design
 - Provides a check that nothing has been missed and that all equipment will function as required
 - Easier and more efficient than performing on site
 - Less confusion and delays when on site for every one that is involved



www.dmdeng.com

DMD & Associates